



Tentative Interim Amendment

NFPA[®] 13

Standard for the Installation of Sprinkler Systems

2019 Edition

Reference: Table 14.2.8.2.1
TIA 19-4
 (SC 19-8-14 / TIA Log #1416)

Pursuant to Section 5 of the NFPA *Regulations Governing the Development of NFPA Standards*, the National Fire Protection Association has issued the following Tentative Interim Amendment to NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2019 edition. The TIA was processed by the Technical Committee on Sprinkler System Installation Criteria, and the Correlating Committee on Automatic Sprinkler Systems, and was issued by the Standards Council on August 6, 2019, with an effective date of August 26 2019.

A Tentative Interim Amendment is tentative because it has not been processed through the entire standards development procedures. It is interim because it is effective only between editions of the standard. A TIA automatically becomes a public input of the proponent for the next edition of the standard; as such, it then is subject to all of the procedures of the standards development process.

1. *Revise Table 14.2.8.2.1 to read as follows:*

Table 14.2.8.2.1 Protection Areas and Maximum Spacing of ESFR Sprinklers

Construction Type	Ceiling/Roof Heights Up to 30 ft (9.1 m)				Ceiling/Roof Heights Over 30 ft (9.1 m)			
	Protection Area		Spacing		Protection Area		Spacing	
	ft ²	m ²	ft	m	ft ²	m ²	ft	m
Noncombustible unobstructed	100	9	12	3.7	100	9	10	3.0
Noncombustible obstructed	100	9	12	3.7	100	9	10	3.0
Combustible unobstructed	100	9	12	3.7	100	9	10	3.0
Combustible obstructed	N/A		N/A		N/A		N/A	
Combustible obstructed	100	9	12	3.7	100	9	10	3.0

Issue Date: August 6, 2019

Effective Date: August 26, 2019

(Note: For further information on NFPA Codes and Standards, please see www.nfpa.org/docinfo)

Copyright © 2019 All Rights Reserved
 NATIONAL FIRE PROTECTION ASSOCIATION